

BRUHATH BANGALORE MAHANAGARA PALIKE

me of work: Improvements of roads and drains in Padma Tent Area in ward No. 07-atarayanapura, Kodigehalli Sub Division.

Description of work	No.	Dimensions			Qty	Rate	Unit	Amount
		L	B	D				
2	3	4	5	6	7	8	9	10
DRAIN								
KSRB 2-2.2:Earth work excavation for foundation of building, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ORDINARY soil not exceeding 1.5m in depth including dressing the bottom and sides of pits and trenches , stacking the excavated soil clear from edges of excavation with lead upto 50m after breaking of clods complete as per specifications and direction of the Engineer-in-charge. Specification. No.KBS 2.1(b)/2.3.5. (P-5, It. No.2.1)								
Basic rate		77.00	✓					
Add A.W. 8%		6.16	✓					
Total		83.16	✓					
over burden earth	1	20.00	1.50	0.60	18.00			
Amruthalli colony road	1	363.00	0.90	0.85	277.70			
CC Drain	1	35.00	0.60	0.30	6.30			
CC Road	1	20.00	5.00	0.30	30.00			
Culvert	1	5.00	1.80	0.90	8.10			
				Total:-	340.10	83.16	Cum	28283.00
2 KSRB 4-1.3: Providing and laying in position plain cement concrete of nominal mix 1:4:8 using 40mm and down size graded granite metal machine mixed, concrete laid in layers not exceeding 15 cms. Thick well compacted in foundation and plinth, including cost of all materials labour, HOM of machinery, curing complete as per specification . (Pg.No.12, It.4.3)						✓	✓	✓
Basic rate		4695.00	✓					
Add A.W. 8%		375.60	✓					
Total		5070.60	✓					
Amruthalli colony road	1	363.00	0.9	0.10	32.67			
CC Drain	1	35	0.6	0.10	2.10			
CC Road	1	20	5	0.10	10.00			
Culvert	1	5	1.8	0.10	0.90			
					45.67	5070.60	Cum	231574.302

SRB4-1.6: Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240 kgs, with 20 mm and down size graded granite matel coarse aggregates @ 0.69 cum and fine aggragtes @ 0.459cum, machine mixed concrete laid in layers not eceeding 15 cms, thick well compacted, in foundation, plinth and cills including cost of all materials, labour HOM machinery curing complete as per specifications. (Page No. 12. Item No. 4.6)

Basic rate		5084.00	✓					
Add A.W. 8%		406.72	✓					
Total		5490.72	✓					
Culvert	1	5	1.8	0.10	0.90			
					0.90	5490.72	Cum	4942.00 ✓



4 **KSRB 4.2.2:** Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320 Kgs with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum with superplastizers @ 3lts confirming to IS 9103-1999 RE affirmed - 2008 machine mixed, concrete laid in layers not exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, stair case lintels, retaining walls return walls, walls(anythickness) including attached plasters columns piers abutments pillars posts struts butresses string or lacing courses parapets copings, bed blocks , plain windows cills fillets etc., including cost of all materials. labour HOM of machinery curing complete as per specifications. **Seocifications No. KBS 4.1,4.6 (Page NO. 13, Item NO. 4.11)+**

Basic rate		5739.00	✓					
Add A.W. 8%		459.12	✓					
Total		6198.12	✓					
CC Drain Bottom								
Amruthalli colony road Main road Drain	1	363.00	0.60	0.10	21.78			
CC Drain	1	35.00	0.60	0.10	2.10			
CC DRAIN SIDEWALL								
Amruthalli colony road	2	363	0.60	0.15	65.34			
CC Drain	2	35.00	0.6	0.15	6.30			
					73.74	6198.12	Cum	457050.00 ✓

SRB 4-9-2: Providing and fabricating TMT . Steel reinforcement for R.C.C. work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps and wastage shall not measured and paid) cost of materials. labour. HOM of machinery complete as per specifications . (Page NO 17, Itm. NO. 4.46.2)									
Basic rate		59327.91	✓		54933.24				
Add A.W. 8%		0.00	✓		4394.66				
Total		59327.91			~~59327.91~~				
Qty @ 60Kg/cum	drain	0.065	X		73.74	4.79			
				Total:-	4.79	59327.91	tonne	284365.00	
KSRB 4-6.4: Providing and removing centering, shuttering strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness including attached pilasters, buttressed, plinth and string courses cost of all materials, labour complete as per specifications (Page no.14, Item No. 4.31)									
Basic Rate		284.00	✓						
Area Weightage 8%		22.72	✓						
total		306.72	✓						
Amruthalli colony road	4	363		0.60	871.20				
Maramma temple street CC Drain	4	35.00		0.60	84.00				
					955.20	306.72	Sqm	292978.94	✓
7 KSRB 4-48: Providing and laying in cement concrete using 20mm and down size granite coarse aggregates and fine aggregates of ready mixed concrete (RMC) for RCC works laid in 15cms thick layers and well compacted vibrating, curing, finishing with necessary cement mortar, with all lead and lifts etc., complete (exclusive of cost of steel and fabrication charges) (Pg No. 18, It No. 4.48)									
Basic rate		5863.00							
Add A.W. 8%		469.04							
Total		6332.04							
CC Road									
	1	20.00	5.00	0.10	10.00				
					10.00	6332.04	Cum	63321.00	✓
8 KSRB 5.3-1: Providing and constructing granite /trap/basalt size stone masonry in foundation with cement mortar 1:6, stone hammered dressed in courses not less than 20cms high, bond stones at two m apart in each course including cost of materials, labour, curing etc., complete as per specifications.(P-235. Item No. 5.3)									

[illegible]

name of work: Improvements to roads and drains in Padma tent area in ward no.07, Vatarayanapura



M. G. N. D.
AE (W&D)

Assistant Executive Engineer
Kodigehalli Sub Division Palike
Kodigehalli Mahanagara Palike
Bijapur - 560 082